

Vergleich der Varianten zur Straßenentwässerung - aufgeteilt nach Straßen

Anlage 2

	Länge [m]	Variante	Mulde [m]	Rigole [m]	Kanal [m]/[€/m]					Fahrbahn [m²]		Zusatzkosten [Psch.]	Varianten, Baukosten [€ Brutto]			
			Kosten [€/m]	Kosten [€/m]	DN 250	DN 300	DN 400	DN 500	DN 600	[€/m]	[€/m]	[€ Brutto]	1	2	3	4
			27,67 €	187,43 €	380,80 €	464,10 €	571,20 €	690,20 €	833,00 €	142,80 €	160,65 €	z.B. RRB				
Tiefenseer Weg	460	1	230	460						2.530			453.863,03 €			
		2			400					2.530				513.604,00 €		
		3			378	58				2.530					532.144,20 €	
		4									2.530					406.444,50 €
Brombeerweg	240	1	120	240						1.320			236.798,10 €			
		2			215					1.320				270.368,00 €		
		3	120	240						1.320					236.798,10 €	
		4									1.320					212.058,00 €
Ginsterweg	595	1	190	595						3.273			584.087,70 €			
Fahrbahn bereits		2			360		225			3.273				732.921,00 €		
überwiegend befestigt		3	190	530	65					3.273					596.657,08 €	
		4									3.273					525.727,13 €
Hagebuttenweg	375	1	190	375						2.063			370.066,20 €			
		2	190	375	365					2.063				509.058,20 €		
		3	190	375						2.063					370.066,20 €	
		4									2.063					331.340,63 €
Kastanienallee	255	1	130	250						1.403		7.500,00 €	258.230,03 €			
nur unbefestigter		2							135	1.403		158.460,40 €		471.192,40 €		
Abschnitt		3					135			1.403		158.460,40 €			435.849,40 €	
		4									1.403					225.311,63 €
Wacholderweg	475	1	240							2.613			379.705,20 €			
Fahrbahn		2	240		236	238				2.613				580.029,80 €		
bereits befestigt		3	240							2.613					379.705,20 €	
		4									2.613					419.698,13 €
Beiersdorfer Weg	545	1	280							2.998			435.789,90 €			
Fahrbahn		2	225		55					2.998				455.212,19 €		
bereits befestigt		3	225		55					2.998					455.212,19 €	
		4									2.998					481.548,38 €
Erlenweg	535	1	260	520						2.943			524.843,55 €			
		2			172	115		248		2.943				710.227,70 €		
		3			58	228	248			2.943					689.747,80 €	
		4									2.943					472.712,63 €
													3.243.383,70 €	4.242.613,29 €	3.696.180,16 €	3.074.841,00 €